

Approaches to Urban Flooding in the City of Blue Island


Jason Berry, AICP jberry@cityofblueisland.org


















The Blue Island...







Deposits left by the glaciers or by the lakes that formed as the glaciers melted are the raw materials of soils. Topography, drainage, climate, and vegetation shape these raw materials into soils. The process takes centuries. In a dynamic landscape, vegetation may change more rapidly than soils. We may find prairies growing on forest soils and forests on prairie soils. The scale of the map allows us to show only broad categories. Small patches of soil that do not match the surrounding land will not appear.


City of Blue Island












- Limited open space
- 8.8% grade
- Cal-Sag channel watershed
- 2 CSOs plus 2 shared CSOs received by Cal-Sag channel



Existing Conditions









• IL Jobs Now / Clean Water Initiative

- Announced October 11, 2014
- Funded IL Green Infrastructure Grants (IGIG, applied 2012; 2013) for NE Neighborhood
- Assistance Amount: \$1,132,588
 - Pervious alleyways, intersection bumpouts and naturalized detention
- City Council approval November 11, 2014




RETENTION POND DETAIL



BIOSWALE DETAIL






Chi-Cal Rivers Fund


- Announced November 18, 2014
- Assistance Amount: \$235,295 (SSMMA)
- 6 acres of wetlands with 1.5MM gallons of stormwater retention
- Remove contaminated soils and plant native vegetation
- Employ students who have graduated from technical environmental training programs



MWRD "Early Out"

- Metropolitan Water Reclamation District Green Infrastructure project
- One of four in the MWRD service area
- Design by Environmental Design Inc. (EDI)
- 8 sites selected
 - 5 Bioswales along Longwood, 1 on Irving
 - 1 permeable pavement site on Longwood, 1 on Irving



















MWRD "Early Out"

- Bid released October 1, 2014
 - Estimated cost of work: \$413,904
- 8 firms attended Oct. 2014 pre-bid; 2 firms submitted
- 5 firms attended April 2015 pre-bid; 3 firms submitted
- Low Bid: \$663,838


Great Lakes Restoration Initiative (GLRI)

- Awarded to South Suburban Mayors and Managers Association (SSMMA)
- Funding Green Infrastructure in Blue Island,
 Robbins and Calumet Park in 2015
- 1,450 SF rain garden with seeding and plugs
- Weaver Boos Consultants providing design
- Job creation: new social enterprise / workforce development initiative with OAI
- City Council to approve IGA



RAIN GARDEN CONSTRUCTION SPECIFICATIONS

- 1. EXCAVATE RAIN GARDEN 2 FEET BELOW FINISHED GRADE.
- INSTALL 2 FEET DEPTH OF ENGINEERED SOIL MIX CONSISTING OF 40% SAND, 30% TOPSOIL, 30% COMPOST. CLEAN EXCAVATED SOIL TO BE USED IN ENGINEERED SOIL MIX WHEN POSSIBLE.
- ENGINEERED SOIL MIX TO BE PLACED ON MONOFILAMENT GEOTEXTILE OVER UNCOMPACTED SOIL
- RAIN GARDEN FINISHED GRADE TO HAVE MINIMUM OF 0'-6" AND MAXIMUM OF 1'-0" DEPRESSION.
- NO EXISTING TREES ARE TO BE REMOVED AS PART OF RAIN GARDEN CONSTRUCTION.
- PLANT PLUGS TO BE (30) 32-CELL FLATS OF 12 DIFFERENT FORBS & GRASSES.
- 7. PLUG TO BE PLANTED AT A DENSITY OF 1 PLUG PER SQUARE FOOT.
- 8. 4" OF MULCH TO BE PLACED OVER PLANT PLUGS AREA.
- 9. SEEDED AREAS TO BE STORMWATER AND ANNUAL & PERENNIAL SEED MIXES
- 10. STRAW EROSION CONTROL FABRIC TO BE PLACED OVER SEEDED AREA.



LEGEND

2000

PROPERTY LINE

EXISTING TREE

CURB CUT
PROPOSED PAVEMENT

PLANT PLUGS, 1,040 SFT


SEEDING, 660 SFT

4' WIDE GRAVEL PATH
INLET PROTECTION


EDUCATIONAL SIGNAGE

EXISTING CATCH BASIN

EXISTING MANHOLE
PROPOSED 6" BARRIER CURB

















MWRD Phase II

- Consultant Agreement with EDI October 31, 2014
- Develop and recommend alternative to flooding problem by July, 2015
 - 6 alternatives
 - 1 recommendation brought to 30% design
- Kick off meeting with MWRD November 14, 2014







MINORITY WORKER TRAINING PROGRAM

Hands-on Training in Environmental Remediation and Basic Carpentry & Construction.


















When it floods, it comes...



WHO WE ARE

WHAT WE DO

WORK WITH US

TOOLS P

PUBLICATIONS

BLOG







CNT calls for Illinois elected leaders to help victims of urban flooding

July 7, 2015



Manny Gonzales

New state study finds 92% of flood damage claims are from homeowners and businesses outside floodplains

SPRINGFIELD – Illinois experienced the wettest June in recorded history as we continue to see an increase in the frequency and intensity of rain events nationwide. This has resulted in more and more flooded homes and businesses, bringing with it the associated costs of property damage,

negative health impacts, loss of work time and a significant loss in property value. A new study & – released on July 6 and mandated by the 2014 Urban Flooding Awareness Act, sponsored by Sen. Heather Steans and Rep. Kelly Cassidy – reveals that more than 92 percent of Illinois flood victims live outside any designated floodplains. The study, prompted by research by the Center for Neighborhood Technology (CNT), dispels the myth that flooding is primarily the result of rivers and streams overflowing their banks.

"The implications of this research for Illinois disaster preparedness are enormous," said Kathryn Tholin, CEO of the non-profit CNT. "We have, for decades, been spending large amounts of taxpayer dollars to solve only one part of the flood damage problem. With this new information, we can adjust our policies and invest our resources in a way that protects a much

BLOG TOPICS

Transportation + Community
Development

Cargo-Oriented Development

Water

Climate

Sustainable Prosperity

Policy

Press Release

VIEW ALL

RECENT POSTS

CNT calls for Illinois elected leaders to help victims of urban flooding

July 7, 2015


CNT Applauds SCOTUS Ruling that Supports Diverse Communities with Access to Jobs

June 26, 2015



RAIN GARDEN CONSTRUCTION SPECIFICATIONS

- 1. EXCAVATE RAIN GARDEN 2 FEET BELOW FINISHED GRADE.
- INSTALL 2 FEET DEPTH OF ENGINEERED SOIL MIX CONSISTING OF 40% SAND, 30% TOPSOIL, 30% COMPOST. CLEAN EXCAVATED SOIL TO BE USED IN ENGINEERED SOIL MIX WHEN POSSIBLE.
- ENGINEERED SOIL MIX TO BE PLACED ON MONOFILAMENT GEOTEXTILE OVER UNCOMPACTED SOIL
- RAIN GARDEN FINISHED GRADE TO HAVE MINIMUM OF 0'-6" AND MAXIMUM OF 1'-0" DEPRESSION.
- NO EXISTING TREES ARE TO BE REMOVED AS PART OF RAIN GARDEN CONSTRUCTION.
- PLANT PLUGS TO BE (30) 32-CELL FLATS OF 12 DIFFERENT FORBS & GRASSES.
- 7. PLUG TO BE PLANTED AT A DENSITY OF 1 PLUG PER SQUARE FOOT.
- 8. 4" OF MULCH TO BE PLACED OVER PLANT PLUGS AREA.
- 9. SEEDED AREAS TO BE STORMWATER AND ANNUAL & PERENNIAL SEED MIXES
- 10. STRAW EROSION CONTROL FABRIC TO BE PLACED OVER SEEDED AREA.



LEGEND

2000

PROPERTY LINE

EXISTING TREE

CURB CUT
PROPOSED PAVEMENT

PLANT PLUGS, 1,040 SFT

SEEDING, 660 SFT

4' WIDE GRAVEL PATH
INLET PROTECTION

EDUCATIONAL SIGNAGE

EXISTING CATCH BASIN

EXISTING MANHOLE
PROPOSED 6" BARRIER CURB

